TUMKUR DIVISION.

Dated 19th November 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division up to 1 P.M., on 19th December 1927, for constructing High School building at Maddagiri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of ..... 192 .

2. The plans and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on all days except Sunday and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing High School building" at Maddagiri in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rate should be noted both in figures and in words in the form without any corrections or additions under items of works.

10. No claim for any higher rate on any account will be entertained after the tender is accepted.

11. The contractor will be fined in terms of his bond for any short progress or delay.

12. By failure to show the stipulated progress monthly, the tender will be liable for removal, fine and forfeiture of earnest money.

13. In matters of any dispute about rates, measurements of work, etc., the decision of Chief Engineer will be final and legally binding.

14. Approximate estimate quantities for constructing High School Building at Maddagiri.

Approximate quantity for constructing High School Building at Maddagiri.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	834
2	Concrete stone jelly in mortar	C.ft.	6976
3	Burnt stone in mortar foundation and basement ...	,,	23891
4	Burnt brick slabs 6" thick cut and fitted dressed ...	S.ft.	1156
5	Arch work burnt brick in mortar cellar portion ...	C.ft.	285
6	Terrace brick on edge excluding concrete 3" and 3 coats of flat tiles and chunam plastering at top, complete.	Sqr.	37·24
7	Steel girders British make including hoisting and rail fright painting two coats lead oxide.	Cwts.	188·53
8	Earth filling in basement including watering and tamping.	C.yd.	468
9	Iron vertical rods ½" dia. teak wood hand rail at top and bottom frame between pillars over cellar portion verandah.	R.ft.	211

No.	Items of work	Per	Quantity
10	Teak wood doors battened shutters frame $5\frac{1}{2}$" x $3\frac{1}{2}$" with iron fittings tower bolts, hinges, lock, etc., complete and painting.	S.ft.	108
11	Teakwood ventilators with expanded metal $\frac{1}{4}$" mesh frame, etc., complete with painting.	,,	144
12	Flooring with 3" concrete plastered over with chunam cellar portion or vajjragarai.	Sqr.	20·17
13	Sundry and other unforeseen items such as cement pointing to exposed portion of basement.	Lumpsum	...
14	Burnt brick in mortar superstructure including bond slabs.	C.ft.	14467
15	Burnt brick in mortar arch work	,,	122
16	Burnt stone slabs 6" thick all exposed parts nicely dressed and fixed in mortar.	S.ft.	966
17	Burnt stone slabs 5" thick two lines nicely dressed with chamferred edges and fixed in mortar and pointed with cement.	,,	495
18	Teakwood doors $1\frac{1}{2}$" thick shutters lower two-thirds panelled and top panel to have wire net with fittings frame and fastening in iron clamps, etc., complete, without bottom rail.	Sqr.	669
19	Teakwood windows $1\frac{1}{4}$" thick single side shutters lower half panelled and upper half glazed shutters in four halves opening outside without iron bars, fittings and fastening including iron clamps, etc., complete including top ventilator.	S.ft	1107
20	Teakwood windows $1\frac{1}{4}$" thick single shutters panelled in four halves with iron bars to laboratory block preparation balance and store, complete.	,,	168
21	Teakwood circular ventilators, glazed shutters, complete frame in gables.	,,	29
22	Teakwood ventilators below, laboratory windows, glazed shutters frame, etc., complete with expanded metal.	,,	49
23	Cast iron gate in passage, complete	,,	36
24	Teakwood wall shelves or almirahs with four glazed shutters, cross planks fittings, etc., complete.	,,	263
25	Trusses with $1\frac{1}{4}$" dia. tie road teak wood principal 3" x 5" Streets 3" x 3" and iron king rod as per design 18' span.	No.	21
26	Teakwood work wrought and put up with oiling ..	C.ft.	689·99
27	Roofing with Mangalore tiles on teak reepers, nails, etc., complete.	Sqr.	120·90
28	Ridge tiles set in mortar and pointed with cement ...	R.ft.	365
29	Valley teakwood planking 1" thick	S.ft.	297
30	Valley zinc sheet	,,	297
31	Teakwood eave board 9" x 1" with silicate painting...	R.ft.	264
32	Teakwood barge board if necessary at entrances in rear verandah.	No.	6
33	Plastering with chunam 2 coats	Sqr.	260·44
34	White and colour washing	,,	260·44
35	Cornice 12" x 9" thick at eaves with string course ...	R.ft.	540
36	Parapet wall	,,	16
37	Chunam band mixed with cement around windows ...	,,	1,364
38	Forming panels below windows	S.ft.	273
39	Flooring with Cuddapah slabs $1\frac{1}{2}$" thick over 3" concrete bed pointed with cement.	Sqr.	1,870
40	Crown of arches and forming panels pillars of wings in front.	Lumpsum	
41	Flooring with square Mangalore tiles on 3" concrete bed and pointed with cement Mysore pattern.	Sqr.	59·82
		,,	417
42	Providing straps, bolts, etc., to pillars	No.	26
43	Silicate painting 2 coats	Sqr.	44·58

No.	Items of work	Per	Quantity
44	Ornamental cast iron semi-circular cover gate in passage.	S.ft.	14
45	Double asbestos sheet screen with teakwood ...	"	417
46	Providing wooden black board similar to the one in Bangalore High School.	Lumpsum	
47	Providing name board and foundation stone laying ceremoney.	"	"
48	Sundry and unforeseen charges ...	"	"
49	Opening out an approach road from the junction to the school.	"	"
50	Ornamental work	"	"
51	Constructing a latrine of 8 seats	"	"
52	Temporary establishment	"	"
53	Laying stoneware drainage pipe diagonally below basement from the open yard at N.-E corner 150 feet long.	"	"
54	Constructing a tiffen shed	"	"
55	Do well	"	"
56	Flue chimney arrangements with hoods, etc. ...	"	"
57	Cost of constructing masonry gallery in steps in the Lecture Hall and Natural Science (3′ wide and rise 8″) of four steps, complete.	"	"
58	Polished Cuddapah or granite slab platform at a height of 2′—10″ from the ground around the balance room with brackets, complete.	S.ft.	32
59	Mangalore pattern glass tiles over roof in balance room and store room,	No.	12

V. V. PATANKAR,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 17th November 1927.

The attention of the public is invited to the notice calling tenders for constructing Barr Huts at Shimoga *vide* pages 1004 and 1005 of the *Mysore Gazette*, Part VI, dated 24th November 1927.

M. A. SRINIVASACHARI,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

MYSORE GOVERNMENT ELECTRICAL DEPARTMENT.

Dated 21st November 1927.

The attention of the public is invited to notification dated 31st October 1927, published in page 963 of Part VI of the *Mysore Gazette* dated 10th November 1927, regarding the sale of Machine parts of the Electrical Department by public auction on the 3rd December 1927 and subsequent dates. The details of materials to be sold are given in the said notification and the materials to be auctioned are open to inspection at the C. P. S. Central Stores near Binny Mills at all working hours, *i.e.*, from 9 A.M. to 12 noon and 2 to 5 P.M. on all working days from 24th November 1927.

B. D. NATH,
Asst. Chief Electrical Engineer.

AMRUT MAHAL DEPARTMENT.

Notification No. A. 2-55-15, *dated 25th November* 1927.

The sale of Amrut Mahal cattle advertised to be held at Sulekere on the 20th and 21st December 1927, *vide* Notification published in the *Mysore Gazette* dated 27th October 1927, is adjourned to the 28th and 29th December 1927.

A. A. MONTEIRO, LIEUT.,
Superintendent,
Amrut Mahal Department.